

Tele/Fax: 2301 5399

SPEED POST/REGISTERED ACK DUE

Dte Gen Md Accn Project
E-in-C's Branch,
Integrated HQ of MoD (Army)
Kashmir House, Rajaji Marg,
New Delhi-110011

82819/MAP/PH-II/PKG-33/ / E8

Jul 2010

M/s. _____

CA NO: DG MAP/PHASE-II/HISSAR/PKG-33 OF 2008-09: CONSTRUCTION OF RESIDENTIAL ACCOMMODATION AT HISSAR

- Reference this HQ letter Nos.82819/MAP/PH-II/PKG-33/248/E8 dated 22 Jul 2010.
- Amendments/errata to the tender documents for the subject work issued vide this HQ letter under reference are as under:-

Srl No.	Page No.	Reference to item, clause, para, line etc.	Particulars of amendments / errata.
1	2	3	4
1.	2	a) Para 2 (a), Lines 4 & 5 b) Para 2 (d), Line 1	For "Appendix 'A' to Notice Inviting Tender" Read " Appendix 'A' to Particular Specifications" For "06 months" Read "04 months"
2.	3	Para 5, Line 5	Delete the words "invitation to" occurring after the word "receiving"
3.	4	Para 1 (a), Line 2	For "6 months" Read "04 months"
4.	6	Para 3.11.1 contd/-, Line 2	For "submitted" Read "submit the same"
5.	8	a) Para 4 (a), Line 6 b) Para 5, Line 2	For "six" Read "four" For "14:30" Read "12:30"
6.	13	a) Note No. 5(c), Line 2 b) -----do----- Line 7	For "CI" Read "UPVC" For "face of the wall" Read " external edge plinth protection"
7.	14	a) Renumbend Note No 5 (f) b) Renumbend Note No 5 (m)	Delete the existing description in toto and insert as under in lieu:- "(f) Numbering of blocks & DUs." Add at the end as under:- "cooler stands"

Contd./

Amendments /Errata (Contd.....)

1	2	3	4
8.	16	a) Note No 14, Line 1 to 3 b) -----do-----, Line 4	Delete the existing description in toto and insert as under in lieu:- "Schedule "A" section I, VII & VIII have not been priced by the Department. The tenderer shall calculate his own rates/lump sum for each items of these schedules and insert his rate/lump sum (both in figures and words) against each item of these schedules and work out his amount in the appropriate column. The total amount of these schedules shall be carried over to General Summary." For "Cost of works in respect of schedule 'A' Section II to IX" Read " Prepriced lump sum amount for works included in respect of schedule 'A' Section II to VI & IX have been worked out by the Department and"
9	20	Srl item 1, Col 2, Line 6	Delete the words "dry out verandahs"
10	22	a) Srl item 3, Col 2, Line 1 b) Srl item 4, Col 2, Line 1 c) Srl item 5, Col 2, Line 1	For "item 3" Read "item 2" For "item 3" Read "item 2" For "item 3" Read "item 2"
11	26	Srl item 17, Col 2, Line 2	For "foil" Read "aluminium foil"
12	52	a) Srl item 16, Col 4 b) Srl item 17, Col 4	For "23.03 Kgs" Read "23.03/Kgs" For "20.31 Running Metre" Read "20.31/Running metre"
13	53	Srl item 20, Col 4	For "72.15 Running metre" Read "72.15/Running metre"
14	65	Srl item 1 (b), Col 2, Line 2	For "heaving" Read "having"
15	66	After Note No 2	Add new Note No. 3 as under:- "3. Before starting site clearance and excavation in trenches for building work, the existing levels of the complete area be taken using Total Station equipment method and plotted on graph sheets. The quantity of earth work shall be worked out with the help of "Simpson's Rule" and shall be entered in MB. The longitudinal and cross sections of the area shall also be plotted on graph sheets. No payment of earth work under site clearance shall be released to the contractor without compliance of these provisions."
16	161	Clause No 4.11	Renumber this clause as "4.1.1"

Amendments /Errata (Contd.....)

1	2	3	4
17	205A	a) Clause 12.3.2 (iv), Line 2 b) -----do----- Line 4 c) After clause 12.3.2 (viii)	For "50=1%" Read "50±1%" For "50=1%" Read "50±1%" Add new clauses as under:- "12.3.2 (ix) Suitable scaffolding to be used shall have sound and strong supports tied together with horizontal pieces over which scaffolding planks shall rest to ensure that no holes are made in the walls for horizontal. 12.3.2 (x) Reflectance test shall be carried out as directed by PM/DEPMC before approval of sample."
18	295	Amendment No 48 (i)	Delete the existing amendment in toto and insert "Blank" in lieu.
19	297	Amendment No 62 (i) to (viii)	Delete the existing amendment in toto and insert "Blank" in lieu.
20	307	Amendment No 98 (i) & (ii)	Delete the existing amendment in toto and insert "Blank" in lieu.
21	1	Para No4, under Col Page No	For "11 to 74" Read "11 to 23, 24(R) 25 to 74."

3. Srl Page No 24 shall be replaced with revised Srl page No 24 (R) enclosed herewith. Revised & cancelled page shall be returned duly signed alongwith tender documents.
4. This letter alongwith enclosures shall form part of the tender documents and shall be returned duly signed with tender documents.
5. The date & time for receipt of tender shall remain unchanged i.e at 12:30 hrs on 18 Aug 2010.

(Mansha Ram)
Jt. Director (Contracts)
for DG MAP

Encls: - As Above

Signature of Contractor

DEPMC

SCHEDULE 'A' SECTION-II (CONTD..../-)
(LIST OF ITEMS OF WORKS & PRICES FOR INTERNAL WATER SUPPLY)

1	2	3	4	5	6
11	Supply and fixing CP brass wall mixer with swinging casted spout and all accessories for mixing hot & cold water, screwed down for 15 mm bore GI pipe complete all as specified.		1644.83/Each	1932	31,77,811.56
12	Supply and fixing 125 mm size chromium plated shower rose with shower arm and swivel joints, complete all as specified.		109.25/Each	1932	2,11,071.00
Total Carried over to Summary of Schedule 'A' Section-II on Serial Page No. 27					Rs 33,88,882.56

Contd.../-